

304-431 Introduction to VLSI CAD (2013) Milestones

Week 1 (September 2)

Team formation completed, DE2 board in your possession

Week 2 (September 9)

- NIOS II tutorial completed, start working on the register file and Qsys component
- Video decoder and DAC models are well advanced.

Week 3 (September 16)

- Qsys system completed with initial version of the register file
- Simulating auto-generated testbench accessing the register file and able to connect to the NIOS through the NIOS II SBT accessing register file (**checkpoint a**)
- C code started, actively coding the timers
- Actively coding the ITU decoder and display controller. Line buffer generated
- Simulating system with video decoder model outputting a frame (**checkpoint b**).

Week 4 (September 23)

- Timers and register file completed
- Debugging NIOS application (**checkpoint b, 2nd chance**).
- Display controller with line buffer able to display a static image on DE2 board (**checkpoint c**).
- Integrating ITU decoder and display controller

Week 5 (September 30)

Actively debugging and getting ready for demo (**checkpoint c, 2nd chance**)

Week 6 (October 7)

- Demo NIOS and display controller
- Final project presentation.

Week 7 (October 14)

Qsys components of SDRAM controller and Grab section generated
Start working on DMA engine
Start working on modifications to the display controller.

Week 8 (October 21)

Integrated SDRAM model to testbench
Integrated PLL into the design
Simulation testbench A (without DMA engine) shows NIOS performing read and write accesses to SDRAM. Simulation testbench B display controller with CSC and line buffer output a mono or a color static image

Week 9 (October 28)

Able to initialize SDRAM memory model through input files. Able to dump SDRAM memory content to a file (**checkpoint d**).
New register file completed
Can start developing C code to control acquisition process. It should also be simulated.

Week 10 (November 4)

System testbench now includes video decoder and SDRAM model. Simulation demonstrates that video decoder data is written into SDRAM (**checkpoint e**).
Partial testbench including display controller and line buffer display static image on monitor (**checkpoint f**).
Add DMA engine to Qsys system.
Actively debug DMA engine.
Start developing C code for processing.

Week 11 (November 11)

Simulation should demonstrate DMA engine fetching correct data from SDRAM and correctly writing to line buffer (**checkpoint g**).
Simulation of the entire system should work, for acquisition, without processing (**checkpoint h**).
First trials to display image on monitor controlled with the NIOS.

Week 12 (November 18)

Debug acquisition on HW.
Place and route of the FPGA completes without critical warnings and all paths are constrained and meet timing requirements.
Add processing capability
Fine-tuned demonstration (sequence of grab, zoom, processing, etc.)

Week 13 (November 25)

- Demo Final Project